ci C I HOST

Address:
1851 Central Drive
3rd Floor
Bedford, TX 76021
USA

Three story building located half-way between downtown Dallas and Fort Worth and directly off of West Airport Freeway (183). Easy access from all suburbs makes this Data Center a prime location for all customers. CDC-01 has four types of co-location available: family (single server), open rack, private rack, and private data vaults. Additionally, C I Host's "e-Business Suites" are available giving any client on-site dedicated work space.

Building Specs:

Square Foot:	35000
Floor Load:	+175 lb./ sq. ft.
Elevators:	Weight capacity 2,000 lbs. 8'6" high, 8.5' wide and 20'6" long.
Ceiling Height:	10 feet above floor
Roof Rights:	Yes, with satellite space available
Line of Sight:	Clear line of sight in all directions
NPA/NXX:	817-868
Fiber:	(2) fiber entry points
Number of Fiber Conduits:	(8) four inch conduits, (2) two inch conduits.
Number of Fiber Interducts:	(8) four inch interducts, (2) one inch interducts with EMT conduit
Core Router:	(2) Cisco 7206VXR
Switching Gear:	(1) Cisco 6500, (100) Cisco Catalyst 2924-XL-EN (100mbps and GigE)

Environmental Controls:

Fire Suppression System:	Pre-action, dry pipe sprinkler system
HVAC:	A/C units maintain a climate of 68 degrees (+/- 5) and 30-60% humidity, N+3 redundancy (200 tons total)

Power Systems:

Standby Generator:	Dedicated 150 kW standby generator

UPS Devices: Compaq 3000W

Security Systems:

- 24x7 On Site Security Personnel
- Quick-locking Mantrap
- Biometric fingerprint ID w/ Card Key Access and Pin-code Backup
- Alarm/Key Monitoring
- CCTV Surveillance

Connectivity (2000mbits total):

Verio	SBC
Looking Glass Networks	Sprint
Qwest	Global Crossing